

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park

Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT**Our File No:** CC6/AIG18005741/UWB3S2**Date:** 28/11/2018REFERENCE

Handling Insurer:	AIG Asia Pacific Insurance Pte. Ltd.	Policy No:	2100179803
Claimant Vehicle No :	SLP7879J	Insured Vehicle No :	SJU7161T
Date of Loss:	28/03/2018	Nature of Claim:	TP
		Claim No:	6698729586SG

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No:	SLP7879J	Engine No:	2NRX158372
Make & Model:	TOYOTA VIOS, 1.5 E (A)	Chassis No:	MHFB29F3002011811
Reg. Date:	19/06/2017 (Man. Year: 2017)	Odometer:	52178 km
Colour:	Silver		
Engine Capacity:	1496 cc		
Market Value/New Car Price:	N/A		
Sum Insured (\$\$):	Market Value/New Car Price		

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition:	Good	Steering (Serviceable):	Yes	Footbrake (Serviceable):	Yes
Handbrake (Serviceable):	Yes	Engine Modification:	No	Pre-accident Condition:	

CONDITION OF TYRES

Front Tyre Size:	195/50R16	Rear Tyre Size:	195/50R16
Front Left Side:	Bridgestone 6 mm	Rear Left Side:	Bridgestone 6 mm
Front Right Side:	Bridgestone 6 mm	Rear Right Side:	Bridgestone 6 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	7,420.48	4,181.88	3,238.60	43.64
Miscellaneous Items	0.00	0.00	0.00	
Labour	4,570.00	2,920.00	1,650.00	36.11
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (\$\$)	11,990.48	7,101.88	4,888.60	40.77
Approved Total (Overridden) (\$\$)		5,650.00		
(\$\$)	11,990.48	5,650.00	6,340.48	52.88
+ GST 7.00/7.00% (\$\$)	839.33	395.50	443.83	52.88
Nett Amount (\$\$)	12,829.81	6,045.50	6,784.31	52.88
+ Loss of Use (8.0 x S\$120.00/day) (\$\$)		960.00		
+ Doc/Search Fee (\$\$)		7.49		
Nett Liability (\$\$)		7,012.99		
Global Sum Settlement (\$\$)		7,000.00		

INSPECTION

Date of Assignment:	28/03/2018	
Date Inspected:	28/03/2018	Inspected At: Pegasus Engineering & Trading Pte Ltd (HQ) 51 DEFU LANE 10 Singapore 539216
Estimated Period of Repair:	6.0 days	

Adjuster: MARCUS CHUA**Manager:** VIVIAN LAU PEI FENG

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*BOOTLID	Dented / Buckled	1,662.40 FL	*762.47 FL
2	1		*BOOTLID LOCK	Twisted	90.40 FL	*90.40 FL
3	1		*BOOTLID LOCK STRIKER	Not Necessary	18.50 FL	*- FL
4	1		*BOOTLID WEATHERSTRIP	Twisted	188.80 FL	*188.80 FL
5	1		*BOOTLID CENTRE LOGO BADGE	Necessary	59.80 FL	*59.80 FL
6	1		*BOOTLID BADGE	Necessary	34.40 FL	*34.40 FL
7	1		*BOOTLID VIOS BADGE	Necessary	44.10 FL	*44.10 FL
8	1		*BOOTLID OUTER GARNISH	Repair	234.30 FL	*- FL
9	1		*BOOTLID INNER TRIM	Not Necessary	234.30 FL	*- FL
10	5		*BOOTLID INNER TRIM CLIPS	Not Necessary	22.50 FL	*- FL
11	2		*BOOTLID HINGE	Repair	115.60 FL	*- FL
12	3		*BOOTLID LOCK CABLE CLIPS	Not Necessary	13.50 FL	*- FL
13	1		*REAR END PANEL	Badly Dented	694.70 FL	*694.70 FL
14	1		*REAR END PANEL INNER TRIM	Twisted	234.30 FL	*234.30 FL
15	2		*REAR LICENCE PLATE LAMP	Not Necessary	128.20 FL	*- FL
16	1		*REAR LUGGAGE FLOOR FOAM	Not Necessary	108.20 FL	*- FL
17	1		*REAR BUMPER	Distorted	502.10 FL	*502.10 FL
18	1		*REAR BUMPER REINFORCEMENT	Dented	379.20 FL	*379.20 FL
19	2		*REAR BUMPER REFLECTOR	Not Necessary	261.60 FL	*- FL
20	2		*REAR BUMPER SIDE RETAINER	Bent	230.20 FL	*230.20 FL
21	2		*REAR BUMPER SIDE HOLDER	Bent	84.00 FL	*84.00 FL
22	10		*REAR BUMPER CLIPS	Necessary	45.00 FL	*45.00 FL
23	2		*REAR BUMPER END SPLASHIELD COVER	Not Necessary	115.00 FL	*- FL
24	2		*REAR LAMP	Cracked	751.60 FL	*751.60 FL
25	4		*REAR LAMP CLIP HOLDER	Not Necessary	17.20 FL	*- FL
26	1		*REAR LAMP PANEL	N/S Bent	248.00 FL	*124.00 FL
27	1		*REAR FENDER N/S	Dented / Bent	969.10 FL	*969.10 FL
28	1		*REAR FENDER INNER TRIM	Deformed / Torn	235.00 FL	*235.00 FL
29	8		*REAR FENDER INNER TRIM CLIPS	Not Necessary	34.40 FL	*- FL
30	1		*REAR EXHAUST BOX	Repair	638.80 FL	*- FL
31	1		*REAR EXHAUST BOX MOUNT	Not Necessary	33.00 FL	*- FL
32	1		*REAR EXHAUST BOX HEAT SHIELD	Not Necessary	59.90 FL	*- FL
33	1		*REAR LICENCE PLATE	Bent	80.00 FS	*40.00 FS
34	1		*REAR LUGGAGE FLOOR PANEL INSULATOR	Not Necessary	250.00 FS	*- FS
35	1		*REAR WINDSHIELD GLASS SEALANT	Necessary	200.00 FS	*40.00 FS
36	1		*REAR WINDSHIELD GLASS SPONGE	Necessary	100.00 FS	*30.00 FS

F=Franchise part. S=SpcNett. L=ListItemDisc.

Sub Total (S\$)	9,118.10	5,539.17
- List Item Discount on L Items 20.00/25.00% (S\$)	1,697.62	1,357.29
Total Parts (S\$)	7,420.48	4,181.88

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
Labour Items				
1	TO CHECK ELECTRICAL LIGHTING CONCERNED.	New	60.00	20.00
2	TO REINSTALL OF REAR BUMPER PARKING SENSOR.	New	120.00	50.00
3	TO RUST-PROOFING OF THE AFFECTED AREAS.	New	180.00	90.00
4	TO TRANSFER BOOTLID FITTINGS, ATTACHMENTS AND PERFORM WATER SEEPAGE TEST.	New	120.00	60.00
5	TO REMOVE AND REFIT INTERIOR FITTINGS, TRIMMINGS, GARNISH AND OTHER, TO ENABLE REPAIR.	New	160.00	80.00
6	TO REMOVE AND REFIT REAR WINDSCREEN GLASS.	New	180.00	120.00
7	TO DROP REAR EXHAUST BOX AND RENEW THE SAME.	New	150.00	0.00
8	PANEL BEATING, KNOCKING AND STRAIGHTEN THE NECESSARY PORTION, REMOVE AND RENEWAL OF PARTS, ADJUST AND REALIGN THE SAME.	New	2,000.00	1,400.00
9	PUTTY AND SPRAY PAINTING OF THE AFFECTED PORTION.	New	1,600.00	1,100.00
Gross Labour Cost (\$)			4,570.00	2,920.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >