

Registration No. QX 383S

S/N	ITEM DESCRIPTION	PARTS				MAN-HOUR QTY
		PARTS QTY	Condition	PARTS COST PER UNIT (\$) AFTER MARK UP	TOTAL PARTS COST (\$) AFTER MARK UP	
1	MATERIALS					
1.1	ROOF TOP PANEL	1	DENTED	\$ 1,300.00	\$ 1,300.00	
1.2	RH ROOF RAILING	1	BENT	\$ 400.00	\$ 400.00	
1.3	INTERIOR CEILING HOLSTERY	1	DEFORMED	\$ 1,350.00	\$ 1,350.00	
1.4	REAR RH DOOR SHELL	1	DENTED	\$ 1,360.00	\$ 1,360.00	
1.5	FRONT WINDSCREEN	1	CRACKED	\$ 1,400.00	\$ 1,400.00	
1.6	FRONT WINDSCREEN MOULDING	1	NECESSARY	\$ 100.00	\$ 100.00	
1.7	SEALANT FOR FRONT WINDSCREEN	1	NECESSARY	\$ 50.00	\$ 50.00	
1.8	PRIMER FOR FRONT WINDSCREEN	1	NECESSARY	\$ 10.00	\$ 10.00	
1.9	FRONT WINDSCREEN SOLAR FIRM	1	NECESSARY	\$ 180.00	\$ 180.00	
1.10	BONNET COVER	1	DENTED	\$ 1,070.00	\$ 1,070.00	
1.11	FRONT BUMPER LOWER GRILLE	1	DEFORMED	\$ 450.00	\$ 450.00	
1.12	TO SUPPLY LABOUR & MATERIAL TO REPLACE BAR LIGHT COVER	1		\$ 1,890.00	\$ 1,890.00	
1	SCOPE OF REPAIRS					
1.1	ROOF TOP PANEL :					38
	REMOVE & RE-INSTALL BAR LIGHT ASSY					
	REMOVE & REPLACE ROOF TOP PANEL (CUT & WELD)					
	REMOVE & REPLACE RH ROOF RAILING					
	PUTTY & SPRAY PAINT FOR ROOF TOP PANEL					
	WATER SEEPAGE TEST FOR ROOF TOP					
1.2	INTERIOR CEILING HOLSTERY :					3
	REMOVE & REPLACE INTERIOR CEILING HOLSTERY					
	REMOVE & RE-INSTALL BACK INTERIOR REAR AIR-CON DUCT & ROOM LIGHT TO FACILITATE THE REMOVAL FOR INTERIOR CEILING HOLSTERY					
1.3	REAR RH DOOR, FRONT LH & RH DOOR :					24
	REMOVE & REPLACE REAR RH DOOR SHELL					

	REMOVE & RE-INSTALL BACK REAR RH DOOR ITEMS (RIOT MESH, WINDOW GLASS, LOCKING MECHANISM, DOOR TRI					
	REPLACE REAR RH DOOR "POLICE" CRESR STICKER (TO BE PROVIDED BY AEMD)					
	ALIGN REAR RH DOOR					
	RE-ALIGN RH DOOR PILLAR					
	RE-ALIGN FRONT LH & RH DOOR					
	PANEL BEATING FOR REAR RH DOOR FRAME					
	PUTTY & SPRAY PAINT FOR REAR RH DOOR FRAME					
	PUTTY & SPRAY PAINT FOR REAR RH DOOR SHELL					
1.4	FRONT WINDSCREEN :					6
	REMOVE & REPLACE FRONT WINDSCREEN					
	REMOVE & REPLACE FRONT WINDSCREEN MOULDING					
	REPLACE FRONT WINDSCREEN SOLAR FIRM					
	WATER SEEPAGE TEST FOR FRONT WINDSCREEN					
1.5	BONNET COVER :					8
	REMOVE & REPLACE FRONT BONNET COVER					
	REMOVE & REPLACE BOTH SIDE BONNET HINGES (LEFT & RIGHT)					
	REPLACE BONNET COVER "POLICE" WORDING STICKER (TO BE PROVIDED BY AEMD)					
	PUTTY & SPRAY PAINT FOR BONNET COVER					
1.6	FRONT BUMPER LOWER GRILLE :					0.5
	REMOVE & REPLACE FRONT BUMPER LOWER GRILL					
1.7	REAR DOOR :					6
	PANEL BEATING FOR REAR DOOR					
	PUTTY & SPRAY PAINT FOR REAR DOOR REPAIRED AREA					
1.8	SPARE TYRE COVER :					1
	REPLACE SPRE TYRE COVER "POLICE" WORDING STICKER (TO BE PROVIDED BY AEMD)					
	PUTTY & SPRAY PAINT FOR SPARE TYRE COVER					
COSTING		TOTAL PARTS COST			\$9,560.00	
		TOTAL MAN-HOUR				86.5

