

Registration No. QX 4834G

S/N	ITEM DESCRIPTION	PARTS				MAN-HOUR QTY
		PARTS QTY	Condition	PARTS COST PER UNIT (\$) AFTER MARK UP	TOTAL PARTS COST (\$) AFTER MARK UP	
1	MATERIALS					
1.1	FRONT WIND SCREEN	1	CRACKED	\$ 375.00	\$ 375.00	
1.2	WIND SCREEN MOULDING	1	NECESSARY	\$ 120.00	\$ 120.00	
1.3	FRONT PANEL	1	DEFORMED	\$ 625.00	\$ 625.00	
1.4	RADIATOR GRILLE	1	DENTED	\$ 250.00	\$ 250.00	
1.5	L/H HEAD LAMP HOUSING	1	BENT	\$ 88.00	\$ 88.00	
1.6	R/H HEAD LAMP	1	MISSING	\$ 300.00	\$ 300.00	
1.7	R/H HEAD LAMP HOUSING	1	MISSING	\$ 88.00	\$ 88.00	
1.8	FRONT BUMPER	1	CRACKED	\$ 320.00	\$ 320.00	
1.9	FRONT BUMPER RETAINER LH	1	UNCONFIRM	\$ 45.00	\$ 45.00	
1.10	FRONT BUMPER RETAINER RH	1	MISSING	\$ 45.00	\$ 45.00	
1.11	DRIVER DOOR COMPLETE ASSY	1	DEFORMED	\$ 2,100.00	\$ 2,100.00	
1.12	R/H WINDOW ASSY	1	MISSING	\$ 550.00	\$ 550.00	
1.13	R/H PANEL	1	DEFORMED	\$ 3,200.00	\$ 3,200.00	
1.14	15" STEEL RIMS RH	2	DENTED	\$ 112.00	\$ 224.00	
1.15	15" STEEL RIMS LH	2	UNCONFIRM	\$ 112.00	\$ 224.00	
1.16	R/H LOWER ARM	1	DENTED	\$ 250.00	\$ 250.00	
1.17	R/H ABSORBER	1	DENTED	\$ 95.00	\$ 95.00	
1.18	R/H UPPER ARM	1	DENTED	\$ 350.00	\$ 350.00	
1.19	L/H LOWER ARM	1	UNCONFIRM	\$ 250.00	\$ 250.00	
1.20	L/H ABSORBER	1	UNCONFIRM	\$ 95.00	\$ 95.00	
1.21	L/H UPPER ARM	1	UNCONFIRM	\$ 350.00	\$ 350.00	
1.22	REAR BUMPER	1	CRACKED	\$ 280.00	\$ 280.00	

1.23	Tyre 15" (SOR 5B_2) CAT B	2	PUNCTURE	\$ 296.21	\$ 592.42	
1	SCOPE OF REPAIRS					
1.1	WIND SCREEN					8
	REMOVE & REPLACE FRONT WIND SCREEN					
	REPLACE FRONT WIND SCREEN MOULDING					
	CUT, WELD & ALIGN WIND SCREEN PILLAR					
	WATER LEAKAGE TEST FOR WIND SCREEN					
	PUTTY & SPRAY PAINT WIND SCREEN PILLAR					
1.2	FRONT PANEL					6
	REMOVE & REPLACE FRONT PANEL					
	PUTTY & SPRAY PAINT FRONT PANEL					
1.3	REMOVE & REPLACE RADIATOR GRILLE					1
1.4	HEAD LAMP					2
	REMOVE & REPLACE L/H HEAD LAMP HOUSING					
	REMOVE & REPLACE R/H HEAD LAMP HOUSING					
	PUTTY & SPRAY PAINT HEAD LAMP HOUSING					
1.5	FRONT BUMPER					6
	REMOVE & REPLACE FRONT BUMPER					
	REPLACE FRONT BUMPER RETAINER					
	REMOVE & REPLACE FRONT BUMPER SUPPORT					
	REPLACE FRONT NUMBER PLATE					
	PUTTY & SPRAY PAINT FRONT BUMPER					
1.6	DASH BOARD					8
	REMOVE & RE-INSTALL DASH BOARD					
	REPAIR & ALIGN DASH BOARD FRAME					
1.7	DRIVER DOOR					22
	REMOVE & REPLACE DRIVER DOOR COMPLETE ASSY					
	CUT, WELD & ALIGN DRIVER DOOR PILLAR					
	PUTTY & SPRAY PAINT DRIVER DOOR & PILLAR					
1.8	CUT, WELD & ALIGN DRIVER FLOOR BOARD					14

	ANTI CORROSION TREATMENT FOR DRIVER FLOOR BOARD					
1.9	REPLACE R/H WINDOW ASSY					2
1.10	CUT, REMOVE & REPLACE R/H PANEL					23
	PUTTY & SPRAY PAINT R/H PANEL					
1.11	TYRE & RIM					4
	REMOVE & REPLACE FRONT R/H TYRE & RIM					
	REMOVE & REPLACE FRONT L/H TYRE & RIM					
	REMOVE & REPLACE REAR R/H TYRE & RIM					
	REMOVE & REPLACE REAR L/H TYRE & RIM					
	PUTTY & SPRAY PAINT ALL TYRE RIM					
1.12	UNDER CARRIAGE					12
	REMOVE & REPLACE R/H LOWER ARM					
	REMOVE & REPLACE L/H LOWER ARM					
	REMOVE & REPLACE R/H ABSORBER					
	REMOVE & REPLACE L/H ABSORBER					
	REMOVE & REPLACE R/H UPPER ARM					
	REMOVE & REPLACE L/H UPPER ARM					
1.13	REPAIR & ALIGN CROSS MEMBER					8
1.14	REPAIR & REPLACE REAR BUMPER					2
	PUTTY & SPRAY PAINT REAR BUMPER					
1.15	REAR CABIN FLOOR BOARD					12
	REMOVE & RE-INSTALL REAR CABIN PASSENGER SEAT					
	CUT, WELD & REPAIR REAR CABIN FLOOR BOARD					
	ANTI CORROSION TREATMENT FOR REAR CABIN FLOOR BOARD					
COSTING		TOTAL PARTS COST			\$10,816.42	
		TOTAL MAN-HOUR				130