5/28/2021 Adjuster Report

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park

Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT

Our File No:

CC3/III19005682/KGA3Q2

Date:

28/05/2021

REFERENCE

Date of Loss:

Handling Insurer: India International Insurance Pte Ltd Policy No:

MCOM0015 SHC8865H

Engine No:

Chassis No:

Odometer:

Claimant Vehicle No: SHD931Y

27/03/2019

Insured Vehicle No: Nature of Claim:

ΤP

Claim No:

MCT19030714

M9R8839C003362

217218 km

VF1ABL15AUC283294

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No: **SHD931Y**

Make & Model: RENAULT LATITUDE, 2.0 L (A) 08/12/2017 (Man. Year: 2015) Reg. Date:

Colour: Metallic White/Red

Engine Capacity: 1995 cc Market Value/New Car Price: N/A

Market Value/New Car Price Sum Insured (S\$):

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition: Good

Steering (Serviceable):

Yes

Footbrake (Serviceable):

Yes

Engine Modification: Handbrake (Serviceable): Yes Pre-accident Condition: No

Giti 7 mm

CONDITION OF TYRES

Front Right Side:

Front Tyre Size: 215/60 R16 Front Left Side: Giti 7 mm

Rear Tyre Size: Rear Left Side: Rear Right Side: 215/60 R16 Giti 9 mm

Giti 9 mm

The above values represent the remaining tyre treads depth

| COST OF CLAIMS | | Repairer's | Adjuster's | Difference | Diff % |
|---------------------|------------------------|------------|------------|------------|--------|
| Parts | | 38,867.35 | 11,782.92 | 27,084.43 | 69.68 |
| Miscellaneous Items | | 0.00 | 0.00 | 0.00 | |
| Labour | | 13,000.00 | 1,470.00 | 11,530.00 | 88.69 |
| Paintwork Labour | | 0.00 | 0.00 | 0.00 | |
| Towing | | 0.00 | 0.00 | 0.00 | |
| | Gross Total (S\$) | 51,867.35 | 13,252.92 | 38,614.43 | 74.45 |
| | + GST 7.00/7.00% (S\$) | 3,630.71 | 927.70 | 2,703.01 | 74.45 |

| Nett Amount (S\$) | 55,498.06 | 14,180.62 | 41,317.44 | 74.45 |
|-------------------|---------------------------|-----------|-----------|-------|
| + Loss of Use (| 6.0 x S\$40.00/day) (S\$) | 240.00 | | |
| + Car Rental (6 | .0 x S\$103.60/day) (S\$) | 621.60 | | |
| | Nett Liability (S\$) | 15,042.22 | | |

INSPECTION

Date of Assignment: 29/03/2019

Trans-cab Auto Services Pte Ltd (Ang Mo Kio) Date Inspected: Inspected At: 29/03/2019

2, Ang Mo Kio Street 63 Singapore 569111

Estimated Period of Repair: 4.0 days

Adjuster: KENNETH KONG Manager: Chong Pui Lin

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly

REPAIR DETAILS

Reference

Part Source: MRM-SG Version: 1.0 (Last Synchronised: 06 Dec 2019)

Parts: 143 RENAULT LATITUDE 2.0 L (A) (Catalogue:Merimen Singapore 1.0)

Labour: Repairer's (Price-denominated Standard List)

Print Code: (Unsubmitted, no print-code for SHD931Y)

Validity: These estimates are valid only if they contain the print code (above) on all estimate pages, running page numbers with the END OF ESTIMATES marker on the last estimate page

Further Info: Items/values not in reference catalogue are prefixed with an asterisk *.

Recommended Parts

| No. | Qty Part No. | Particulars | Condition | Repairer's | Amount |
|-----|--------------|--------------------------------|-------------|-------------|--------------|
| 1 | 1 | *BUMPER COVER FRT | Bent | 1,259.42 FL | *1,259.42 FL |
| 2 | 1 | *BUMPER SPOILER FRT | Serviceable | 181.75 FL | *- FL |
| 3 | 1 | *BUMPER ABSORBER FRT | Cracked | 394.68 FL | *394.68 FL |
| 4 | 1 | *BUMPER RETAINER FRT LH | Distorted | 151.41 FL | *151.41 FL |
| 5 | 1 | *BUMPER SUPPORT FRT | Serviceable | 123.88 FL | *-FL |
| 6 | 1 | *BUMPER RETAINER FRT RH | Distorted | 150.77 FL | *150.77 FL |
| 7 | 1 | *BUMPER SUPPORT FRT | Serviceable | 123.88 FL | *-FL |
| 8 | 1 | *BUMPER UNDERTRAY FRT | Serviceable | 472.83 FL | *- FL |
| 9 | 1 | *BUMPER GRILLE LOWER FRT | Cracked | 266.80 FL | *266.80 FL |
| 10 | 1 | *BUMPER FOG LAMP GRILLE LH | Serviceable | 207.21 FL | *- FL |
| 11 | 1 | *BUMPER FOG LAMP GRILLE RH | Serviceable | 207.21 FL | *- FL |
| 12 | 1 | *BUMPER BEAM FRT | Bent | 914.08 FL | *914.08 FL |
| 13 | 1 | *TOW COVER FRT | Serviceable | 28.61 FL | *- FL |
| 14 | 1 | *RADIATOR GRILLE | Cracked | 1,707.78 FL | *1,707.78 FL |
| 15 | 1 | *RADIATOR GRILLE BADGE RENAULT | Necessary | 225.36 FL | *225.36 FL |
| 16 | 1 | *RADIATOR GRILLE FRAME | Cracked | 1,353.75 FL | *1,353.75 FL |
| 17 | 1 | *FRAME FULL SUPPORT PANEL | Cracked | 615.90 FL | *615.90 FL |
| 18 | 1 | *FRAME FULL SUPPORT BRACKET | Bent | 89.79 FL | *89.79 FL |
| 19 | 1 | *FRONT BRACE PANEL | Bent | 177.22 FL | *177.22 FL |
| 20 | 1 | *HORN | Serviceable | 314.17 FL | *- FL |
| 21 | 1 | *HORN BRACKET | Repair | 40.45 FL | *- FL |
| 22 | 1 | *HEADLAMP RH | Mtg Cracked | 1,184.43 FL | *1,184.43 FL |
| 23 | 1 | *HEADLAMP HARNESS | Serviceable | 928.29 FL | *- FL |
| 24 | 1 | *HEADLAMP PANEL FRT RH | Bent | 152.15 FL | *152.15 FL |
| 25 | 1 | *BONNET | Bent | 1,941.63 FL | *1,941.63 FL |
| 26 | 1 | *BONNET INSULATOR | Serviceable | 405.73 FL | *- FL |
| 27 | 1 | *BONNET STRUT LH | Serviceable | 88.61 FL | *- FL |

| No. Qty Part No. | Particulars | Condition | Repairer's | Amount |
|------------------|--|-------------|-------------|--------------|
| 28 1 | *BONNET STRUT RH | Serviceable | 88.61 FL | *- FL |
| 29 1 | *BONNET HINGE LH | Repair | 348.31 FL | *- FL |
| 30 1 | *BONNET HINGE RH | Repair | 348.31 FL | *- FL |
| 31 1 | *BONNET LOCK | Distorted | 305.48 FL | *305.48 FL |
| 32 1 | *BONNET CABLE | Serviceable | 119.19 FL | *- FL |
| 33 1 | *BONNET CABLE COVER | Serviceable | 161.03 FL | *- FL |
| 34 1 | *BONNET SEAL OUTER | Serviceable | 92.36 FL | *- FL |
| 35 1 | *BONNET SEAL INNER | Serviceable | 157.28 FL | *- FL |
| 36 1 | *FENDER PANEL FRT LH | Repair | 783.83 FL | *- FL |
| 37 1 | *WHEELARCH FRT LH | Serviceable | 278.84 FL | *- FL |
| 38 1 | *FENDER BRACKET LOWER LH | Serviceable | 15.79 FL | *- FL |
| 39 1 | *FENDER PANEL FRT LH | Repair | 783.83 FL | *- FL |
| 40 1 | *FENDER INSULATOR LH | Serviceable | 130.84 FL | *- FL |
| 41 1 | *FENDER PANEL INNER FRT LH | Repair | 1,693.77 FL | *- FL |
| 42 1 | *FENDER PANEL FRT RH | Repair | 783.83 FL | *- FL |
| 43 1 | *FENDER INSULATOR RH | Serviceable | 130.84 FL | *- FL |
| 44 1 | *FENDER PANEL INNER FRT RH | Repair | 1,693.77 FL | *- FL |
| 45 1 | *TURBO DUCT | Serviceable | 1,027.80 FL | *- FL |
| 46 1 | *A/C HEATER VALVE | Serviceable | 484.50 FL | *- FL |
| 47 1 | *SUBFRAME OUTER FRT | Serviceable | 2,652.45 FL | *- FL |
| 48 1 | *SUBFRAME BRACKET OUTER LH | Serviceable | 92.36 FL | *- FL |
| 49 1 | *SUBFRAME BRACKET OUTER RH | Serviceable | 92.36 FL | *- FL |
| 50 1 | *ENGINE UNDERTRAY | Serviceable | 564.98 FL | *- FL |
| 51 1 | *A/C CONDENSER | Bent | 2,020.37 FL | *2,020.37 FL |
| 52 1 | *A/C CONDENSER GARNISH LH UPPER | Serviceable | 39.67 FL | *- FL |
| 53 1 | *A/C CONDENSER GARNISH RH UPPER | Serviceable | 39.67 FL | *- FL |
| 54 1 | *A/C CONDENSER GARNISH LH | Serviceable | 58.81 FL | *- FL |
| 55 1 | *A/C CONDENSER GARNISH RH | Serviceable | 59.60 FL | *- FL |
| 56 1 | *A/C PIPE CONDENSER TO COMPRESSOR | Serviceable | 208.39 FL | *- FL |
| 57 1 | *A/C PIPE CONDENSER TO EXPANSION VALVE | Serviceable | 658.72 FL | *- FL |
| 58 1 | *A/C PIPE COMPRESSOR | Serviceable | 334.29 FL | *- FL |
| 59 1 | *A/C PIPE | Serviceable | 658.72 FL | *- FL |
| 60 1 | *A/C COMPRESSOR | Serviceable | 2,684.61 FL | *- FL |
| 61 1 | *AIR COOLER | Serviceable | 792.60 FL | *- FL |
| 62 1 | *AIR INTERCOOLER HOSE (LONG) | Serviceable | 1,014.13 FL | *- FL |
| 63 1 | *AIR INTERCOOLER HOSE (SHORT) | Serviceable | 375.14 FL | *- FL |
| 64 1 | *TRANSMISSION COOLER ` | Serviceable | 1,219.30 FL | *- FL |
| 65 1 | *TRANSMISSION COOLER PAD | Serviceable | 17.96 FL | *- FL |
| 66 1 | *RADIATOR | Serviceable | 1,202.20 FL | *- FL |
| 67 2 | *RADIATOR STUD UPPER | Serviceable | 14.41 FL | *- FL |

Report was unsubmitted during this print-out.

| No. Qty Part No. | Particulars | Condition | Repairer's | Amount |
|-------------------------|------------------------------------|--|-------------|-----------|
| 68 2 | *RADIATOR BUSH UPPER | Serviceable | 50.12 FL | *- FL |
| 9 2 | *RADIATOR MTG LOWER | Serviceable | 55.85 FL | *- FL |
| '0 1 | *RADIATOR FAN COWLING | Serviceable | 820.54 FL | *- FL |
| 1 1 | *RADIATOR FAN MOTOR LH | Serviceable | 967.36 FL | *- FL |
| 2 1 | *RADIATOR FAN MOTOR RH | Serviceable | 1,479.46 FL | *- FL |
| 3 1 | *RADIATOR TANK | Serviceable | 324.62 FL | *- FL |
| 4 1 | *RADIATOR HOSE UPPER | Serviceable | 240.56 FL | *- FL |
| 5 1 | *RADIATOR HOSE LOWER | Serviceable | 491.18 FL | *- FL |
| 6 1 | *RADIATOR TANK HOSE | Serviceable | 61.18 FL | *- FL |
| 7 1 | *SET RADIATOR GRILLE FRAME CLIP | Necessary | 52.00 FS | *52.00 FS |
| 3 1 | *SET BUMPER CLIP FRT | Necessary | 66.00 FS | *66.00 FS |
| 9 1 | *BUMPER BRACKET CLIP FRT LH | Not Necessary | 12.00 FS | *- FS |
|) 1 | *BUMPER SUPPORT CLIP FRT LH | Not Necessary | 10.50 FS | *- FS |
| 1 1 | *BUMPER BRACKET CLIP FRT RH | Not Necessary | 12.00 FS | *- FS |
| 2 1 | *BUMPER SUPPORT CLIP FRT RH | Not Necessary | 10.50 FS | *- FS |
| 3 1 | *TOW COVER FRT | Serviceable | 14.50 FS | *- FS |
| 4 1 | *SET RADIATOR GRILLE SCREW | Not Necessary | 16.00 FS | *- FS |
| 5 1 | *SET BUMPER GRILLE LOWER CLIP | Not Necessary | 69.00 FS | *- FS |
| 3 1 | *SET FRAME FULL SUPPORT PANEL CLIP | Not Necessary | 70.00 FS | *- FS |
| 7 2 | *FRAME FULL SUPPORT PANEL NUT | Not Necessary | 20.00 FS | *- FS |
| 3 2 | *FRAME FULL SUPPORT PANEL STUD | Not Necessary | 30.00 FS | *- FS |
| 9 1 | *WINDSCREEN MOULDING | Not Necessary | 100.00 FS | *- FS |
| 0 1 | *FRONT NUMBER PLATE WITH HOLDER | Bent | 200.00 FS | *45.00 FS |
| Franchise part. S=SpcNe | tt. L=ListItemDisc. | | | |
| | | Sub Total (S\$) | 43,110.11 | 13,074.02 |
| | | - List Item Discount on L Items 10.00/10.00% (S\$) | 4,242.76 | 1,291.10 |
| | | Total Parts (S\$) | 38,867.35 | 11,782.92 |

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

| No | Particulars | Lab.Type | Repairer's | Amount |
|------------|--|----------------|------------|----------|
| <u>Lab</u> | our Items | | | |
| 1 | PANEL BEATING, KNOCKING AND STRAIGHTENING THE NECESSARY PORTION, REMOVE AND RENEWAL OF PARTS, ADJUST AND REALIGN THE SAME. | New | 4,000.00 | 500.00 |
| 2 | TOWING FEES. | New | 120.00 | 50.00 |
| 3 | TO APPLY PAINT PROTECTION SYSTEM (PPS) MAINTAIN AND ENHANCEMENT. | New | 380.00 | 0.00 |
| 4 | PUTTY AND SPRAY PAINTING OF THE AFFECTED PORTION. | New | 4,000.00 | 660.00 |
| 5 | TO RUST-PROOFING OF THE AFFECTED AREAS. | New | 170.00 | 60.00 |
| 6 | TO REMOVE AND REFIT INTERIOR FITTINGS, TRIMINGS, GARNISH, FITTINGS AND OTHER, TO ENABLE REPAIR. | New | 380.00 | 0.00 |
| 7 | TO CHECK STEERING GEOMETRY AND COMPUTER WHEEL ALIGNMENT. | New | 220.00 | 0.00 |
| 8 | TO PULL AND JACK OUT CHASSIS FRAME AND CORRECT IT TO SYMMETRICAL POSITION WITH THE AID OF HYDRAULIC PNEUMATIC. | New | 380.00 | 0.00 |
| 9 | LABOUR CHARGE TO MOUNT AND DISMOUNT VEHICLE ON JIG BENCH, TO FACILITATE REPAIR. | New | 380.00 | 0.00 |
| 10 | TO LIFT-UP ENGINE WITH GEAR BOX AND REFIT. | New | 440.00 | 0.00 |
| 11 | TO REMOVE AND RENEW POWER STEERING PUMP, OIL COOLER PIPE AND FINAL CHECKING AND TESTING. | New | 440.00 | 0.00 |
| 12 | TO REMOVE AND REFIT AIR BAG SYSTEM AND RESET. | New | 480.00 | 0.00 |
| 13 | TO DROP DIESEL TANK, PIPES, HOSES TO FACILITATE BODYWORK REPAIR, FINAL CHECKING AND TESTING. | New | 380.00 | 0.00 |
| 14 | TO VACUUM, REPLACE, REFIX AND RECHARGE AIR CONDENSER. | New | 380.00 | 100.00 |
| 15 | TO REPLACE, REFIX AND TOP UP COOLANT FOR RADIATOR. | New | 170.00 | 50.00 |
| 16 | TO VACUUM, REPLACE, REFIX AND RECHARGE AIR INTERCOOLER. | New | 170.00 | 50.00 |
| 17 | TO TRANSFER OF FENDER FITTINGS, ATTACHMENTS AND PERFORM WATER SEEPAGE TEST. | New | 170.00 | 0.00 |
| 18 | TO TRANSFER OF BONNET FITTINGS, ATTACHMENTS AND PERFORM WATER SEEPAGE TEST. | New | 170.00 | 0.00 |
| 19 | TO TRANSFER OF DOOR FITTINGS, ATTACHMENTS AND PERFORM WATER SEEPAGE TEST. | New | 170.00 | 0.00 |
| | Gross Labo | our Cost (S\$) | 13,000.00 | 1,470.00 |

Report was unsubmitted during this print-out.

< END OF ESTIMATES >