

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park
Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT

Our File No: CC6/AIG20001188/KES3Q2

Date: 29/04/2020

REFERENCE

Handling Insurer: AIG Asia Pacific Insurance Pte. Ltd. Policy No: 1900142812
Claimant
Vehicle No : SLD8433T **Insured Vehicle No :** SMN5157X
Date of Loss: 18/01/2020 Nature of Claim: TP Claim No: 5385057351SG

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No: **SLD8433T**
Make & Model: HONDA VEZEL, 1.5 (A) Engine No: L15B4029092
Reg. Date: 29/06/2016 (Man. Year: 2015) Chassis No: RU11109088
Colour: Metallic Black Odometer: 90396 km
Engine Capacity: 1496 cc
Market Value/New Car Price: N/A
Sum Insured (S\$): **Market Value/New Car Price**

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition: Steering (Serviceable): Yes Footbrake (Serviceable): Yes
Handbrake (Serviceable): Yes Engine Modification: No Pre-accident Condition: Yes

CONDITION OF TYRES

Front Tyre Size: 215/55 R17 Rear Tyre Size: 215/55 R17
Front Left Side: Michelin 6 mm Rear Left Side: Michelin 7 mm
Front Right Side: Michelin 6 mm Rear Right Side: Michelin 7 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	7,302.99	5,981.12	1,321.87	18.10
Miscellaneous Items	0.00	0.00	0.00	
Labour	3,950.00	2,900.00	1,050.00	26.58
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (S\$)	11,252.99	8,881.12	2,371.87	21.08
Approved Total (Overridden) (S\$)		7,100.00		
(S\$)	11,252.99	7,100.00	4,152.99	36.91
+ GST 7.00/7.00% (S\$)	787.71	497.00	290.71	36.91
Nett Amount (S\$)	12,040.70	7,597.00	4,443.70	36.91
+ Car Rental (18.0 x S\$100.00/day + 7.00% GST) (S\$)		1,926.00		
+ Doc/Search Fee (S\$)		2.00		
Nett Liability (S\$)		9,525.00		

INSPECTION

Date of Assignment: 20/01/2020
Date Inspected: 20/01/2020 Inspected At: 9A SERANGOON NORTH AVE 5
SINGAPORE 554500
Repairer: Optima Werkz Pte Ltd (HQ)
Estimated Period of Repair: 11.0 days

Adjuster: KENNETH KONG

Manager: Asher Sng Rong Yi

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*REAR TAILGATE	Bent	972.40 FL	*972.40 FL
2	1		*REAR TAILGATE VEZEL EMBLEM	Necessary	45.80 FL	*45.80 FL
3	1		*REAR TAILGATE PULL HANDLE	Dented	42.60 FL	*42.60 FL
4	1		*REAR TAILGATE INNER LOCK	Dented	136.00 FL	*136.00 FL
5	1		*REAR TAILGATE RUBBER	Deformed	198.00 FL	*198.00 FL
6	1		*REAR TAILGATE INNER TRIM	Buckled	278.60 FL	*278.60 FL
7	10		*REAR TAILGATE INNER TRIM CLIPS	Necessary	66.00 FL	*66.00 FL
8	1		*REAR WINDSCREEN RUBBER	Necessary	74.40 FL	*74.40 FL
9	1		*REAR END PANEL	Bent	478.90 FL	*478.90 FL
10	1		*REAR END PANEL UPPER COVERING	Distorted	208.80 FL	*208.80 FL
11	6		*REAR END PANEL UPPER COVERING CLIPS	Necessary	39.00 FL	*39.00 FL
12	1		*REAR SPARE TYRE PANEL UPPER BOARD COVER	Deformed	590.80 FL	*590.80 FL
13	1		*REAR SPARE TYRE PANEL UPPER TRAY COVER	Buckled	492.60 FL	*492.60 FL
14	1		*REAR TOOL KIT TRAY BOX FOAM	Serviceable	273.50 FL	*- FL
15	1		*REAR TRUNK LID INNER SIDE TRAIL COVERING RH	Serviceable	426.40 FL	*- FL
16	1		*REAR BUMPER	Bent	787.90 FL	*787.90 FL
17	8		*REAR BUMPER CLIPS	Necessary	46.40 FL	*46.40 FL
18	1		*REAR BUMPER REFLECTOR RH	Cracked	153.60 FL	*153.60 FL
19	1		*REAR SIDE BUMPER RH	Buckled	161.10 FL	*161.10 FL
20	1		*REAR SIDE BUMPER BRACKET RH	Repair	45.90 FL	*- FL
21	1		*REAR TAIL LAMP RH	Mtg Cracked	487.50 FL	*487.50 FL
22	1		*REAR UNDER COVER ASSY	Serviceable	157.30 FL	*- FL
23	1		*REAR EXHAUST PIPE	Bent	922.50 FL	*922.50 FL
24	1		*REAR QUARTER PANEL RH	Buckled	770.00 FL	*770.00 FL
25	1		*REAR QUARTER PANEL INNER LINER RH	Serviceable	174.44 FL	*- FL
26	4		*REAR QUARTER PANEL INNER LINER CLIPS RH	Not Necessary	24.80 FL	*- FL
27	1		*REAR WHEEL ARCH EXTENTION COVER RH	Distorted	186.00 FL	*186.00 FL
28	1		*REAR FLOOR PANEL(NPA)	Repair	0.00 FL	*- FL
29	1		*REAR WINDSCREEN SEALANT	Necessary	80.00 FS	*40.00 FS
30	1		*REAR BUMPER REVERSE SENSOR	Dented	350.00 FS	*200.00 FS
31	1		*REAR END PANEL JOINT SEALANT	Necessary	30.00 FS	*30.00 FS
32	1		*REAR FLOOR PANEL INSULATION PADDING	Not Necessary	250.00 FS	*- FS

F=Franchise part. S=SpcNett. L=ListItemDisc.

Sub Total (\$)	8,951.24	7,408.90
- List Item Discount on L Items 20.00/20.00% (\$)	1,648.25	1,427.78
Total Parts (\$)	7,302.99	5,981.12

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
Labour Items				
1	LABOUR CHARGES TO REMOVE ,REPLACE ,REPAIR ,READJUST REAR ACCIDENT AREAS & ETC	New	1,600.00	1,400.00
2	LABOUR CHARGES TO REMOVE ,REFIX ,REPLACE REAR WINDSCREEN SEALANT ,REAR WINDSCREEN GLASS ,REAR WINDSCREEN RUBBER & ETC .TO EFFECT REPLACE OF REAR TAILGATE &ETC	New	150.00	120.00
3	LABOUR CHARGES TO REMOVE ,REPLACE ,REFIX REAR EXHAUST PIPE ,REAR EXHAUST PIPE HANGER & ETC	New	120.00	60.00
4	LABOUR CHARGES TO REMOVE,REPLACE REAR BUMPER REVERSE SENSOR & ETC	New	80.00	50.00
5	LABOUR CHARGE TO REMOVE & REINSTALLED REAR TAILGATE INNER MECHANISM & ETC	New	120.00	60.00
6	LABOUR CHARGES FOR PAINTING & TO SUPPLY PAINT & FURNISHING MATERIALS AT REAR BUMPER,REAR TAILGATE ,REAR END PANEL,REAR FLOOR PANEL ,REAR SIDE BUMPER RH ,REAR QUATER PANEL & ETC	New	1,600.00	1,100.00
7	TO TUFF KOTE & UNDERSEAL MATERIALS	New	200.00	90.00
8	TO CHECK WIRING & CENTRAL LOCKING SYSTEM & ETC	New	80.00	20.00
Gross Labour Cost (\$\$)			3,950.00	2,900.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >