

LKK Auto Consultants Pte Ltd

(Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park

Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com; assignments@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT

Our File No: CC3/III20005601/KEA3Q2

Date: 13/08/2020

REFERENCE

Handling Insurer:	India International Insurance Pte Ltd	Policy No:	D19MFL0005549
Claimant Vehicle No :	SHB7793T	Insured Vehicle No :	GBJ3825R
Date of Loss:	02/05/2020	Nature of Claim:	TP
		Claim No:	MFL2020D0000916

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No:	SHB7793T		
Make & Model:	TOYOTA PRIUS, 1.8 5DR HATCHBACK (A)	Engine No:	2ZR2C43488
Reg. Date:	16/08/2019 (Man. Year: 2018)	Chassis No:	JTDKB3FU703082712
Colour:	Metallic Pearl White/Red	Odometer:	120370 km
Engine Capacity:	1798 cc		
Market Value/New Car Price:	N/A		
Sum Insured (S\$):	Market Value/New Car Price		

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition:	Steering (Serviceable):	Yes	Footbrake (Serviceable):	Yes
Handbrake (Serviceable):	Yes	Engine Modification:	No	Pre-accident Condition:

CONDITION OF TYRES

Front Tyre Size:	195/65 R15	Rear Tyre Size:	195/65 R15
Front Left Side:	Sailun 8 mm	Rear Left Side:	Sailun 7 mm
Front Right Side:	Sailun 8 mm	Rear Right Side:	Sailun 7 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	6,896.42	1,153.57	5,742.85	83.27
Miscellaneous Items	0.00	0.00	0.00	
Labour	15,340.00	1,460.00	13,880.00	90.48
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Gross Total (S\$)	22,236.42	2,613.57	19,622.85	88.25
+ GST 7.00/7.00% (S\$)	1,556.55	182.95	1,373.60	88.25
Nett Amount (S\$)	23,792.97	2,796.52	20,996.45	88.25
+ Loss of Use (9.0 x S\$40.00/day) (S\$)		360.00		
+ Car Rental (9.0 x S\$148.10/day) (S\$)		1,332.90		
+ Doc/Search Fee (S\$)		7.49		
Nett Liability (S\$)		4,496.91		
Global Sum Settlement (S\$)		4,490.00		

INSPECTION

Date of Assignment: 06/05/2020

Date Inspected: 06/05/2020 Inspected At:

Trans Cab Auto Services Pte Ltd -
Amk (HQ)
No 2 Ang Mo Kio St 63
Singapore 569111

Estimated Period of Repair: 5.0 days

Adjuster: KENNETH KONG**Manager:** Asher Sng Rong Yi

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Reference

Part Source:	MRM-SG	Version: 1.0 (Last Synchronised: 30 Jul 2020)
Parts:	144	TOYOTA PRIUS 1.8 5DR HATCHBACK (A) (Catalogue:Merimen Singapore 1.0)
Labour:	Repairer's	(Price-denominated Standard List)
Print Code:	(Unsubmitted, no print-code for SHB7793T)	
Validity:	These estimates are valid only if they contain the print code (above) on all estimate pages, running page numbers with the END OF ESTIMATES marker on the last estimate page	
Further Info:	Items/values not in reference catalogue are prefixed with an asterisk *.	

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*MOULDING ASSY ,BODY ROCKER PANEL LH	Repair	594.80 FL	*- FL
2	1		*PANEL SUB-ASSY ,QUARTER LH	Bent	871.50 FL	*871.50 FL
3	1		*REAR FENDER LINER	Serviceable	139.80 FL	*- FL
4	1		*DUCT ASSY ,QUARTER VENT ,LH	Serviceable	67.00 FL	*- FL
5	1		*SEAL ,REAR BUMPER SIDE ,LH	Serviceable	88.50 FL	*- FL
6	1		*REAR BUMPER	Buckled / Dented	442.60 FL	*442.60 FL
7	1		*REAR BUMPER UNDER COVER (BLACK)	Serviceable	576.30 FL	*- FL
8	1		*REAR BUMPER SIDE RETAINER LH	Serviceable	116.50 FL	*- FL
9	1		*TAILLAMP LOWER LH	Serviceable	502.00 FL	*- FL
10	1		*TAILLAMP UPPER LH	Serviceable	451.80 FL	*- FL
11	1		*REAR BUMPER SIDE LH	Serviceable	123.70 FL	*- FL
12	1		*PANEL SUB-ASSY ,REAR DOOR ,LH	Repair	1,294.90 FL	*- FL
13	1		*HANDLE ASSY ,REAR DOOR OUTSIDE ,LH	Serviceable	97.40 FL	*- FL
14	1		*TAPE ,BLACK OUT ,NO.1 LH	Not Necessary	21.90 FL	*- FL
15	1		*TAPE ,BLACK OUT ,NO.2 LH	Not Necessary	34.90 FL	*- FL
16	1		*TAPE ,BLACK OUT ,NO.3 LH	Not Necessary	15.40 FL	*- FL
17	1		*REAR WHEEL RIM	Serviceable	1,879.40 FL	*- FL
18	1		*REAR WHEEL RIM COVER	Serviceable	211.50 FL	*- FL
19	1		*REAR DOOR STICKER 6555-3333	Necessary	100.00 FS	*60.00 FS
20	1		*SET REAR BUMPER CLIP	Necessary	68.00 FS	*68.00 FS
21	2		*REAR WINDSCREEN SEALANT	Not Necessary	140.00 FS	*- FS
22	1		*WINDSCREEN MOULDING	Not Necessary	180.00 FS	*- FS
23	1		*REAR WINDSCREEN INNER SPONGE SEAL	Not Necessary	120.00 FS	*- FS
24	1		*SET REAR FENDER LINER CLIP	Not Necessary	38.00 FS	*- FS
25	1		*REAR TYRE 195/65/15	Serviceable	350.00 FS	*- FS
26	1		*SET REAR BUMPER RETAINER CLIP	Not Necessary	38.00 FS	*- FS
27	1		*SET ROCKER PANEL MOULDING CLIP	Not Necessary	35.00 FS	*- FS
28	1		*SET TAILLAMP LOWER CLIP	Not Necessary	30.00 FS	*- FS
29	1		*SET TAILLAMP UPPER CLIP	Not Necessary	30.00 FS	*- FS
30	1		*REAR BUMPER PROTECTOR	Necessary	120.00 FS	*40.00 FS

F=Franchise part. S=SpcNett. L=ListItemDisc.

Sub Total (\$)	8,778.90	1,482.10
- List Item Discount on L Items 25.00/25.00% (\$)	1,882.48	328.53
Total Parts (\$)	6,896.42	1,153.57

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
<u>Labour Items</u>				
1	TO TRANSFER OF REAR FENDER FITTINGS ,ATTACHMENTS AND PERFORM WATER SEEPAGE TEST }	New	170.00	100.00
2	TO REMOVE AND REFIT INTERIOR FITTINGS,TRIMINGS,GARNISH,FITTINGS AND OTHER ,TO ENABLE REPAIR }	New	380.00	0.00
3	TO CHECK STEERING GEOMETRY AND COMPUTER WHEEL ALIGNMENT	New	220.00	0.00
4	TO TRANSFER OF REAR BUMPER FITTINGS ,ATTACHMENTS AND PERFORM WATER SEEPAGE TEST	New	170.00	0.00
5	TO TRANSFER OF REAR WINDSCREEN GLASS TO FACILITATE BODYWORK REPAIR	New	170.00	0.00
6	PANEL BEATING ,KNOCKING AND STRAIGHTENING THE NECESSARY PORTION,REMOVE AND RENEWAL OF PARTS ,ADJUST AND REALIGN THE SAME	New	6,500.00	600.00
7	TO REINSTALL REAR BUMPER PARKING SENSOR	New	170.00	50.00
8	LABOUR CHARGE TO MOUNT AND DISMOUNT VEHICLE ON JIG BENCH ,TO FACILITATE REPAIR	New	380.00	0.00
9	PUTTY AND SPRAY PAINTING OF THE AFFECTED PORTION	New	6,500.00	660.00
10	TO CHECK ELECTRICAL LIGHTING CONCERNED	New	170.00	20.00
11	TO RUST PROOFING OF THE AFFECTED AREAS	New	170.00	30.00
12	TO TRANSFER OF TIRE ,RIM AND ON WHEEL BALANCING	New	170.00	0.00
13	TO TRANSFER OF DOOR FITTINGS ,ATTACHMENTS AND PERFORM WATER SEEPAGE TEST	New	170.00	0.00
Gross Labour Cost (\$\$)			15,340.00	1,460.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >