

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park

Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT**Our File No:** CC4/III21009812/VRA3Q2**Date:** 16/12/2021REFERENCE

Handling Insurer: India International Insurance Pte Ltd Policy No: D19MFL0005549_01

Claimant Vehicle No : SKR7398G **Insured Vehicle No :** GBK4229A

Date of Loss: 17/09/2021 Nature of Claim: TP Claim No: MFL2021D0004184

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No: **SKR7398G**

Make & Model: TOYOTA COROLLA ALTIS, 1.6 CVT (A) Engine No: 1ZR492132

Reg. Date: 04/03/2015 (Man. Year: 2015) Chassis No: MR053REH104527466

Colour: White Odometer: 123647 km

Engine Capacity: 1598 cc

Market Value/New Car Price: N/A

Sum Insured (S\$): **Market Value/New Car Price**

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition: Steering (Serviceable): Yes Footbrake (Serviceable): Yes

Handbrake (Serviceable): Yes Engine Modification: No Pre-accident Condition:

CONDITION OF TYRES

Front Tyre Size: 205/55 R16 Rear Tyre Size: 205/55 R16

Front Left Side: Yokohama 6 mm Rear Left Side: Yokohama 6 mm

Front Right Side: Yokohama 6 mm Rear Right Side: Yokohama 6 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	8,441.60	1,789.36	6,652.24	78.80
Miscellaneous Items	0.00	0.00	0.00	
Labour	4,870.00	1,570.00	3,300.00	67.76
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (S\$)	13,311.60	3,359.36	9,952.24	74.76
Approved Total (Overridden) (S\$)		2,700.00		
Nett Amount (S\$)	13,311.60	2,700.00	10,611.60	79.72
+ Car Rental (5.0 x S\$100.00/day) (S\$)		500.00		
(S\$)		3,200.00		
Liabe Amount (50.00%) (S\$)		1,600.00		
+ Doc/Search Fee (S\$)		7.45		
Nett Liability (S\$)		1,607.45		

INSPECTION

Date of Assignment: 20/09/2021

Date Inspected: 21/09/2021 Inspected At:

AUTO BULLOX PTE LTD - ubi (HQ)
53 UBI AVENUE 1 #01-25 PAYA UBI INDUSTRIAL
PARK
Singapore 408934

Estimated Period of Repair: 4.0 days

Adjuster: Thevan Thomas Karthikesavan**Manager:** Jaslin Kok Chin Yi

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Reference

Part Source: MRM-SG Version: 1.0 (Last Synchronised: 21 Oct 2021)

Parts: 143 TOYOTA COROLLA ALTIS 1.6 CVT (A) (Catalogue:Merimen Singapore 1.0)

Labour: Repairer's (Price-denominated Standard List)

Print Code: (Unsubmitted, no print-code for SKR7398G)

Validity: These estimates are valid only if they contain the print code (above) on all estimate pages, running page numbers with the END OF ESTIMATES marker on the last estimate page

Further Info: Items/values not in reference catalogue are prefixed with an asterisk *.

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*BOOTLID PANEL	Repair	986.40 FL	*- FL
2	1		*BOOTLID WEATHERSTRIP	Serviceable	295.50 FL	*- FL
3	1		*BOOTLID INNER LOCK	Jammed	286.20 FL	*159.00 FL
4	2		*BOOTLID HINGE	Bent	156.00 FL	*156.00 FL
5	1		*BOOTLID LOGO	Necessary	94.20 FL	*94.20 FL
6	1		*BOOTLID EMBLEM COROLLA	Necessary	67.50 FL	*45.60 FL
7	1		*BOOTLID EMBLEM ALTIS	Necessary	72.40 FL	*41.00 FL
8	1		*BOOTLID OUTER GARNISH	Serviceable	295.60 FL	*- FL
9	1		*BOOTLID INNER TRIM GARNISH	Serviceable	286.70 FL	*- FL
10	1		*SET BOOTLID INNER TRIM GARNISH CLIPS	Not Necessary	48.00 FL	*- FL
11	1		*BOOTLID LAMP O/S	Cracked	545.70 FL	*328.00 FL
12	1		*REAR WINDSCREEN GLASS MOULDING	Not Necessary	195.40 FL	*- FL
13	1		*TAILLAMP O/S	Cracked	786.50 FL	*374.45 FL
14	1		*TAILLAMP PANEL O/S	Repair	214.50 FL	*- FL
15	1		*REAR BUMPER	Cut	925.50 FL	*581.90 FL
16	2		*REAR BUMPER SIDE RETAINER	Necessary	137.00 FL	*137.00 FL
17	2		*REAR BUMPER BRACKET	Necessary	128.40 FL	*96.00 FL
18	1		*REAR BUMPER REINFORCEMENT	Repair	320.80 FL	*- FL
19	1		*REAR BUMPER SPONGE	Serviceable	115.60 FL	*- FL
20	1		*REAR BUMPER REFLECTOR O/S	Cracked	196.40 FL	*58.00 FL
21	1		*REAR FENDER O/S	Repair	1,086.70 FL	*- FL
22	1		*REAR FENDER INNER SHIELD O/S	Serviceable	297.40 FL	*- FL
23	1		*SET REAR FENDER INNER SHIELD CLIPS	Necessary	48.00 FL	*48.00 FL
24	1		*REAR FENDER INNER TRIM GARNISH O/S	Serviceable	386.70 FL	*- FL
25	1		*SET REAR FENDER INNER TRIM GARNISH CLIPS	Serviceable	55.00 FL	*- FL
26	1		*REAR FENDER AIR-VENT GARNISH O/S	Serviceable	128.60 FL	*- FL
27	1		*END PANEL TOP GARNISH	Serviceable	286.40 FL	*- FL
28	1		*SET END PANEL TOP GARNISH CLIPS	Serviceable	38.00 FL	*- FL
29	1		*END PANEL	Repair	678.50 FL	*- FL
30	1		*REAR EXHAUST BOX	Serviceable	955.20 FL	*- FL
31	2		*REAR EXHAUST MOUNTING	Serviceable	136.00 FL	*- FL
32	1		*REAR EXHAUST MUFFLER	Repair	158.00 FL	*- FL
33	1		*SET REAR NUMBER PLATE W/GARNISH	Serviceable	55.00 FS	*- FS
34	1		*SET REVERSE SENSOR	Cut	280.00 FS	*200.00 FS
35	1		*REAR WINDSCREEN PRIMER & CLEANER	Not Necessary	100.00 FS	*- FS
36	1		*REAR WINDSCREEN SEALANT	Not Necessary	80.00 FS	*- FS
37	1		*REAR WINDSCREEN INNER SEAL	Not Necessary	60.00 FS	*- FS
38	1		*REAR WINDSCREEN SEALANT	Not Necessary	60.00 FS	*- FS

F=Franchise part. S=SpcNett. L=ListItemDisc.

Sub Total (\$\$)	11,043.80	2,319.15
- List Item Discount on L Items 25.00/25.00% (\$\$)	2,602.20	529.79
Total Parts (\$\$)	8,441.60	1,789.36

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
Labour Items				
1	TO REMOVE ,REPLACE ,RE-ALIGN & INSTALL AFFECTED REAR DAMAGED AREAS	New	1,800.00	600.00
2	TO PUTTY ,PREP & RE-SPRAY ON AFFECTED REAR DAMAGED AREAS (REAR BUMPER ,BOOTLID,END PANEL,REAR FENDERS ,SPARE TYRE PANEL)	New	1,800.00	800.00
3	TO REMOVE & TRANSFER REAR BOOTLID COMPONENTS ,TO FACILITATE REPAIRS	New	150.00	0.00
4	TO REMOVE & REFIT REAR INTERIOR FLOOR COMPONENTS TO FACILITATE REPAIRS	New	150.00	40.00
5	TO REMOVE & INSTALL REAR WINDSCREEN GLASS TO FACILITATE REPAIRS	New	150.00	0.00
6	TO REMOVE & INSTALL REAR EXHAUST PIPE TO FACILITATE REPAIRS	New	150.00	0.00
7	TO MEASURE DRILL HOLES ON REPLACED REAR BUMPER ,TO RE-POSITION & INSTALL REVERSE SENSOR	New	150.00	40.00
8	TO CONDUCT WATER SEEPAGE TEST	New	120.00	30.00
9	TO DISCONNECT REAR WIRE HARNESS ELECTRICAL COMPONENTS TO FACILITATE REPAIRS	New	120.00	30.00
10	TO APPLY UNDERCOATING ON THE AFFECTED DAMAGED AREAS	New	280.00	30.00
Gross Labour Cost (S\$)			4,870.00	1,570.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >