

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park

Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT

AIG Asia Pacific Insurance Pte. Ltd.
AIG Building, 78 Shenton Way, #09-16
Singapore 079120

Our File No: CS/AIG21013200/R1QF3E2

Date: 27/01/2022

REFERENCE

Insured/Claimant:	ANG KOK PENG	Policy No:	7210093332		
Date of Loss:	23/12/2021	Nature of Claim:	OD	Claim No:	4557012697SG

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No:	SBB266R	Engine No:	G4FGMH703099
Make & Model:	KIA CERATO, 1.6 (A)	Chassis No:	KNAF3416MM5107363
Reg. Date:	19/08/2021 (Man. Year: 2021)	Odometer:	2639 km
Colour:	White		
Engine Capacity:	1591 cc		
Market Value/New Car Price:	S\$96,000.00		
Sum Insured (S\$):	Market Value/New Car Price		

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition:	Steering (Serviceable):	Yes	Footbrake (Serviceable):	Yes
Handbrake (Serviceable):	Yes	Engine Modification:	No	Pre-accident Condition:

CONDITION OF TYRES

Front Tyre Size:	225/40 R18	Rear Tyre Size:	225/40 R18
Front Left Side:	Firenza 6 mm	Rear Left Side:	Firenza 6 mm
Front Right Side:	Firenza 6 mm	Rear Right Side:	Firenza 6 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	4,520.20	4,161.80	358.40	7.93
Miscellaneous Items	0.00	0.00	0.00	
Labour	2,750.00	1,960.00	790.00	28.73
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (S\$)	7,270.20	6,121.80	1,148.40	15.80
- Excess (S\$)	300.00	300.00	0.00	0.00
(S\$)	6,970.20	5,821.80	1,148.40	16.48
+ GST 7.00/7.00% (S\$)	487.91	407.53	80.38	16.47
Nett Amount (S\$)	7,458.11	6,229.33	1,228.78	16.48

INSPECTION

Date of Assignment:	28/12/2021	
Date Inspected:	28/12/2021 Inspected At:	Cycle & Carriage KIA Pte Ltd (Pandan Gardens) 209 Pandan Gardens Singapore 609339
Estimated Period of Repair:	3.0 days	

Adjuster: MOHD RASUL

Manager: SHIAU CHAN

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*SUNDRIES	Necessary	40.00 FS	*20.00 FS
2	1		*LAMP ASSY-HEAD, LH	Scratched	1,219.00 FL	*1,219.00 FL
3	1		*COVER-FR BUMPER	Cracked	633.00 FL	*633.00 FL
4	1		*GRILLE-FRONT BUMPER	Cracked	262.00 FL	*262.00 FL
5	1		*MOULDING-FRONT BUMPER, LH	Cracked	36.00 FL	*36.00 FL
6	1		*LAMP ASSY-FRONT FOG, LH	Not Necessary	303.00 FL	*- FL
7	1		*LAMP ASSY-SIDE REPEATER, LH	Scratched	143.00 FL	*143.00 FL
8	1		*ABSORBER-FRONT BUMPER ENERGY	Not Necessary	84.00 FL	*- FL
9	1		*AIR DUCT-FR BUMPER, LH	Not Necessary	14.00 FL	*- FL
10	1		*BRACKET-FR BUMPER UPR SIDE MTG	Not Necessary	22.00 FL	*- FL
11	1		*NEW K3 2020 BODYKIT	Missing	1,721.00 FS	*1,721.00 FS
12	1		*CARRIER ASSY - FRONT END MODULE (Supplementary)	Cracked	675.00 FL	*675.00 FL
13	1		*COOLANT (4L) (Supplementary)	Necessary	26.00 FL	*26.00 FL
14	1		*ORNAMENT - KIA NO. 115 (Supplementary)	Necessary	32.00 FL	*32.00 FL

F=Franchise part. S=SpcNett. L=ListItemDisc.

Sub Total (S\$)	5,210.00	4,767.00
- List Item Discount on L Items 20.00/20.00% (S\$)	689.80	605.20
Total Parts (S\$)	4,520.20	4,161.80

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
Labour Items				
1	REPLACE FRT BUMPER, BODY KIT & AFFECTED AREA	New	800.00	400.00
2	PAINT WORK ON FRT BUMPER & BODY KIT	New	1,050.00	700.00
3	REMOVE & INSTALL FRT BODY KIT	New	80.00	80.00
4	TO APPLY SEALANT ON AFFECTED AREA	New	40.00	0.00
5	CHECK WIRING & ELECTRICAL SYSTEM	New	30.00	30.00
6	TO CARRY OUT DIAGNOSTIC CHECK ON ELECTRONIC CONTROL SYSTEM	New	120.00	120.00
7	VACUUM & TOP UP AIRCON GAS (Supplementary)	New	80.00	80.00
8	REPLACE FRONT SUPPORT PANEL (Supplementary)	New	400.00	400.00
9	REMOVE & REFIT AIRCON CONDENSER & RADIATOR (Supplementary)	New	150.00	150.00
Gross Labour Cost (S\$)			2,750.00	1,960.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >