LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park
Singapore 408933
Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com;cs-a@lkkauto.com;admin-a@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT

Our File No:	CS/CTI22005534/EVY3Q2
Date:	28/03/2023

REFERENCE

Handling Insurer:	China Taiping Insurance (Singapore) Pte. Ltd.	Policy No:	DMPCSNW00111332202
Claimant Vehicle No :	SLC9420D	**Insured Vehicle No :**	SLZ5501J
Date of Loss:	23/05/2022	Nature of Claim: TP	Claim No: SNM22D203603/C02/TANKL

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No:	**SLC9420D**		
Make & Model:	HONDA SHUTTLE, 1.5 G (A)	Engine No:	L15B3536506
Reg. Date:	30/05/2016 (Man. Year: 2016)	Chassis No:	GK81005546
Colour:	Blue	Odometer:	326353 km
Engine Capacity:	1496 cc		
Market Value/New Car Price:	N/A		
Sum Insured (S$):	**Market Value/New Car Price**		

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition:		Steering (Serviceable):	Yes	Footbrake (Serviceable):	Yes
Handbrake (Serviceable):	Yes	Engine Modification:	No	Pre-accident Condition:	

CONDITION OF TYRES

Front Tyre Size:	185/55 R15	Rear Tyre Size:	185/55 R15
Front Left Side:	Dunlop 4 mm	Rear Left Side:	Dunlop 4 mm
Front Right Side:	Dunlop 4 mm	Rear Right Side:	Dunlop 4 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	3,732.00	1,777.60	1,954.40	52.37
Miscellaneous Items	0.00	0.00	0.00	
Labour	1,380.00	1,290.00	90.00	6.52
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (S$)	**5,112.00**	**3,067.60**	**2,044.40**	**39.99**
Approved Total (Overridden) (S$)		**2,450.00**		
(S$)	5,112.00	2,450.00	2,662.00	52.07
+ GST 8.00/8.00% (S$)	408.96	196.00	212.96	52.07
Nett Amount (S$)	**5,520.96**	**2,646.00**	**2,874.96**	**52.07**

INSPECTION

Date of Assignment:	10/06/2022		
Date Inspected:	10/06/2022	Inspected At:	LION CITY RENTALS (HQ) NO. 4 JALAN BESUT Singapore 619557
Estimated Period of Repair:	5.0 days		

Adjuster:	CHEN TSUE YEE	**Manager:**	VERON CHEN

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Reference

Part Source:		(Last Synchronised: 28 Mar 2023)
Parts:	N/A	HONDA SHUTTLE 1.5 G (A) (Model not available in database)
Labour:	Repairer's	(Price-denominated Standard List)
Print Code:	(Unsubmitted, no print-code for SLC9420D)	
Validity:	These estimates are valid only if they contain the print code (above) on all estimate pages, running page numbers with the END OF ESTIMATES marker on the last estimate page	
Further Info:	Items/values not in reference catalogue are prefixed with an asterisk *.	

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		***R/L FENDER**	Dented	2,000.00 FL	*1,172.00 FL
2	1		***R/L FENDER INNER LINER**	Not Necessary	240.00 FL	*- FL
3	1		***R/L DOOR**	Dented	1,575.00 FL	*1,050.00 FL
4	1		***LH SIDE SKIRT**	Repair	750.00 FL	*- FL
5	1		***SET REAR LH FENDER INNER LINEAR CLIPS**	Not Necessary	80.00 FS	*- FS

F=Franchise part. S=SpcNett. L=ListItemDisc.

	Repairer's	Amount
Sub Total (S$)	**4,645.00**	**2,222.00**
- List Item Discount on L Items 20.00/20.00% (S$)	913.00	444.40
Total Parts (S$)	**3,732.00**	**1,777.60**

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items
There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
	Labour Items			
1	**TO REMOVE FRONT BUMPER ,F/L FENDER OUT TO FACILITATE REPAIRS AND REPLACEMENT OF DAMAGED PARTS**	New	600.00	600.00
2	**TO RESPRAY REAR LH FENDER ,REAR DOOR LH AND LH SIDE SKIRT**	New	700.00	660.00
3	**TO APPLY RUSTPROOFING /TUFFCOATING TREAMENT TO REPLACED PARTS**	New	80.00	30.00
	Gross Labour Cost (S$)		**1,380.00**	**1,290.00**

Report was unsubmitted during this print-out.

< END OF ESTIMATES >