

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park
Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com;cs-a@lkkauto.com;admin-a@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORTIndia International Insurance Pte Ltd
64 Cecil Street, #04-00 IOB Building
Singapore 049711**Our File No:** CS/III22008010/KCY3E2**Date:** 17/03/2023REFERENCE

Insured/Claimant: COMFORTDELGRO RENT-A-CAR PTE LTD Policy No: D18MFL0003414_03

Date of Loss: 28/07/2022

Nature of Claim: OD

Claim No: MFL2022D0004130

DESCRIPTION & IDENTIFICATION OF VEHICLEReg No: **SNC7652R**

Make & Model: TOYOTA NOAH HYBRID, 1.8 (A)

Engine No: 2ZR2M88904

Reg. Date: 15/11/2021 (Man. Year: 2021)

Chassis No: ZWR800507226

Colour: Metallic Silver

Odometer: 51978 km

Engine Capacity: 1797 cc

Market Value/New Car Price: S\$163,000.00

Sum Insured (S\$): **Market Value/New Car Price**CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition: Steering (Serviceable): Yes Footbrake (Serviceable): Yes

Handbrake (Serviceable): Yes Engine Modification: No Pre-accident Condition:

CONDITION OF TYRES

Front Tyre Size: 195/65 R15

Rear Tyre Size: 195/65 R15

Front Left Side: Yokohama 3 mm

Rear Left Side: Yokohama 6 mm

Front Right Side: Yokohama 3 mm

Rear Right Side: Yokohama 6 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	17,682.97	12,937.22	4,745.75	26.84
Miscellaneous Items	11.00	11.00	0.00	0.00
Labour	3,340.00	2,460.00	880.00	26.35
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (S\$)	21,033.97	15,408.22	5,625.75	26.75
- Excess (S\$)	0.00	1,500.00	-1,500.00	
(S\$)	21,033.97	13,908.22	7,125.75	33.88
+ GST 7.00/8.00% (S\$)	1,472.38	1,112.66	359.72	24.43
Nett Amount (S\$)	22,506.35	15,020.88	7,485.47	33.26

INSPECTION

Date of Assignment: 22/08/2022 Present Location: ComfortDelGro Engineering Pte Ltd (Braddell)

Date Inspected: 22/08/2022 Inspected At: ComfortDelGro Engineering Pte Ltd (Braddell)

205 Braddell Road

Singapore 579701

Estimated Period of Repair: 8.0 days

Adjuster: KENNETH KONG**Manager:** CELINE FONG*NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.*

Different 1 cents -Finalise confirm amount: \$15,408.23

REPAIR DETAILS

Reference

Part Source:	MRM-SG	Version: 1.0 (Last Synchronised: 17 Mar 2023)
Parts:	M1-MPV	TOYOTA NOAH HYBRID 1.8 (A) (Catalogue:Merimen Singapore 1.0)
Labour:	Repairer's	(Price-denominated Standard List)
Print Code:	(Unsubmitted, no print-code for SNC7652R)	
Validity:	These estimates are valid only if they contain the print code (above) on all estimate pages, running page numbers with the END OF ESTIMATES marker on the last estimate page	
Further Info:	Items/values not in reference catalogue are prefixed with an asterisk *.	

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*FRT BUMPER	Repair	823.20 FL	*- FL
2	1		*FRT BUMPER LH RETAINER	Distorted	105.60 FL	*105.60 FL
3	1		*LH HEADLAMP	Mtg Cracked	3,606.60 FL	*3,606.60 FL
4	1		*FRT LH FENDER	Bent	1,115.40 FL	*911.20 FL
5	1		*FRT LH FENDER INNER SHEILD	Cracked	182.60 FL	*182.60 FL
6	1		*FRT LH FENDER INNER SHIELD CLIP	Necessary	50.00 FL	*50.00 FL
7	1		*FRT LH FENDER QUATER GLASS	Serviceable	238.30 FL	*- FL
8	1		*FRT LH DOOR	Bent	1,774.10 FL	*1,672.30 FL
9	1		*FRT LH DOOR HINGE TOP	Repair	95.40 FL	*- FL
10	1		*FRT LH DOOR HINGE LOWER	Bent	95.40 FL	*95.40 FL
11	1		*FRT LH DOOR CHECKER	Serviceable	101.50 FL	*- FL
12	1		*LH WING MIRROR ASSY	Serviceable	1,390.40 FL	*- FL
13	1		*FRT LH DOOR OUTER MOULDING	Dented	148.70 FL	*148.70 FL
14	1		*FRT LH DOOR STICKER (BLACK)	Necessary	240.50 FL	*240.50 FL
15	1		*FRT LH DOOR WHEATHERSTRIP	Cut	380.40 FL	*380.40 FL
16	1		*FRT LH DOOR LOCK MECHANISM	Jammed	410.70 FL	*410.70 FL
17	1		*FRT LH DOOR LOWER INNER RUBBER SEAL	Cut	105.60 FL	*105.60 FL
18	1		*FRT LH DOOR GLASS	Serviceable	610.60 FL	*- FL
19	1		*FRT LH DOOR OUTER HANDLE	Distorted	385.40 FL	*385.40 FL
20	1		*FRT LH DOOR HANDLE SEAL 1	Necessary	21.50 FL	*21.50 FL
21	1		*FRT LH DOOR HANDLE SEAL 2	Necessary	20.40 FL	*20.40 FL
22	1		*LH CEBTER PILLAR OUTER	Bent	580.30 FL	*580.30 FL
23	1		*REAR LH SLIDING DOOR	Bent	1,847.30 FL	*1,594.00 FL
24	1		*REAR LH SLIDING DOOR RUBBER	Cut	1,364.00 FL	*1,160.00 FL
25	1		*REAR LH SLIDING DOOR STICKER (BLACK)	Necessary	158.50 FL	*158.50 FL
26	1		*LH ROCKER PANEL GARNISH	Buckled	480.50 FL	*480.50 FL
27	1		*FRT LH RIM 15	Dented	1,850.40 FL	*850.00 FS
28	1		*FRT LH TYRE (NPA)	Serviceable	-	*- FL
29	1		*FRT LH WHEEL HUB	Bent	215.60 FL	*215.60 FL
30	1		*FRT LH WHEEL HUB BEARING	Necessary	140.30 FL	*140.30 FL
31	1		*FRT LH KNUCKLE	Bent	329.70 FL	*329.70 FL
32	1		*FRT LH LOWER ARM	Distorted	580.50 FL	*566.60 FL
33	1		*FRT LH ABSORBER	Bent	380.30 FL	*380.30 FL
34	1		*FRT LH ABSORBER TOP MOUNTING	Serviceable	140.20 FL	*- FL
35	1		*STEERING LH TIE ROD	Bent	98.70 FL	*98.70 FL
36	1		*STEERING RACK	Bent / Jammed	2,074.90 FL	*2,074.90 FL
37	1		*FRT LH STABILIZER LINK	Serviceable	105.20 FL	*- FL
38	1		*FRT LH DRIVESHAFT	Repair	1,328.60 FL	*- FL

F=Franchise part. S=SpcNett. L=ListItemDisc.

Sub Total (\$\$) **23,577.30** **16,966.30**
- List Item Discount on L Items 25.00/25.00% (\$\$) 5,894.33 4,029.08

Report was unsubmitted during this print-out.

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
					Total Parts (S\$)	17,682.97
						12,937.22

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

No	Qty	Particulars	Repairer's	Amount
<u>Miscellaneous Items</u>				
1	1	OD/TP Case (Insurer)	11.00	11.00
Sub Total (\$)			11.00	11.00

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
<u>Labour Items</u>				
1	TO KNOCK & STRAIGHTEN ON ACCIDENT AREA, TO REMOVE & REFIT LH SIDE DAMAGE PARTS	New	1,400.00	1,000.00
2	TO PUTTY & RESPRAY ON LEFT SIDE AFFECTED AREA	New	1,400.00	1,000.00
3	TO CHECK WIRING, FOCUS HEADLAMP	New	100.00	20.00
4	TO REMOVE & REFIT UNDERCARRIAGE TO ASSIST WORK LOAD	New	200.00	200.00
5	TO DO WHEEL ALIGNMENT	New	80.00	80.00
6	TO REMOVE & REFIT DOOR TRIM, DOOR GLASS, WINDOW REGULATOR, DOOR LOCK TO ASSIST WORKLOAD	New	160.00	160.00
Gross Labour Cost (\$)			3,340.00	2,460.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >