

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park

Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com;assignments@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT**Our File No:** CC4/AIS22008316/APA3Q2**Date:** 29/12/2022REFERENCE

Handling Insurer:	Allianz Insurance Singapore Pte. Ltd.	Policy No:	SP2001691485
Claimant Vehicle No :	SML6151R	Insured Vehicle No :	GBB8128D
Date of Loss:	17/08/2022	Nature of Claim:	TP
		Claim No:	202222006249

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No:	SML6151R	Engine No:	A25A0117898
Make & Model:	TOYOTA CAMRY, 2.5 G HYBRID CVT (A)	Chassis No:	AXVH701023344
Reg. Date:	28/05/2019 (Man. Year: 2018)	Odometer:	40252 km
Colour:	Black		
Engine Capacity:	2487 cc		
Market Value/New Car Price:	N/A		
Sum Insured (S\$):	Market Value/New Car Price		

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition:	Steering (Serviceable):	Yes	Footbrake (Serviceable):	Yes
Handbrake (Serviceable):	Yes	Engine Modification:	No	Pre-accident Condition:

CONDITION OF TYRES

Front Tyre Size:	215/65 R17	Rear Tyre Size:	215/65 R17
Front Left Side:	Michelin 6 mm	Rear Left Side:	Michelin 6 mm
Front Right Side:	Michelin 6 mm	Rear Right Side:	Michelin 6 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	10,891.01	4,265.32	6,625.69	60.84
Miscellaneous Items	0.00	0.00	0.00	
Labour	4,250.00	1,910.00	2,340.00	55.06
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (S\$)	15,141.01	6,175.32	8,965.69	59.21
Approved Total (Overridden) (S\$)		4,900.00		
Nett Amount (S\$)	15,141.01	4,900.00	10,241.01	67.64
+ Loss of Use (7.0 x S\$100.00/day) (S\$)		700.00		
+ Doc/Search Fee (S\$)		7.45		
Nett Liability (S\$)		5,607.45		

INSPECTION

Date of Assignment:	29/08/2022	JL Perfect Autowork Pte Ltd (HQ)
Date Inspected:	30/08/2022 Inspected At:	8 Kaki Bukit Avenue 4, #08-09 Premier@Kaki Bukit
Estimated Period of Repair:	6.0 days	Singapore 415875

Adjuster: ADRIAN LING**Manager:** CHEW HSIAO TONG

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Reference

Part Source:	MRM-SG	Version: 1.0 (Last Synchronised: 29 Dec 2022)
Parts:	143	TOYOTA CAMRY 2.5 G HYBRID CVT (A) (Catalogue:Merimen Singapore 1.0)
Labour:	Repairer's	(Price-denominated Standard List)
Print Code:	(Unsubmitted, no print-code for SML6151R)	
Validity:	These estimates are valid only if they contain the print code (above) on all estimate pages, running page numbers with the END OF ESTIMATES marker on the last estimate page	
Further Info:	Items/values not in reference catalogue are prefixed with an asterisk *.	

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*REAR BUMPER	Deformed	625.70 FL	*625.70 FL
2	1		*REAR BUMPER DIFFUSER	Deformed	393.50 FL	*393.50 FL
3	2		*REAR BUMPER REFLECTOR	Not Necessary	251.20 FL	*- FL
4	2		*REAR BUMPER SIDE RETAINER (SIDE)	Damaged	256.60 FL	*256.60 FL
5	1		*REAR BUMPER REINFORCEMENT	Dented	319.70 FL	*319.70 FL
6	2		*REAR BUMPER REINFORCEMENT BRACKET	Not Necessary	342.40 FL	*- FL
7	2		*TAILLAMP	Not Necessary	1,780.40 FL	*- FL
8	2		*TAILLAMP SIDE GARNISH	Not Necessary	60.20 FL	*- FL
9	2		*TAILLAMP LOWER BRACKET	Not Necessary	119.20 FL	*- FL
10	2		*REAR FENDER INNER COWLING	Not Necessary	437.20 FL	*- FL
11	2		*REAR FENDER INNER TRIM	Not Necessary	1,581.80 FL	*- FL
12	1		*BOOTLID	Buckled	1,143.70 FL	*1,143.70 FL
13	2		*BOOTLID LAMP	Not Necessary	1,231.00 FL	*- FL
14	1		*BOOTLID LOGO	Necessary	49.80 FL	*49.80 FL
15	1		*BOOTLID EMBLEM HYBRID	Necessary	59.80 FL	*59.80 FL
16	2		*BOOTLID HINGE	Not Necessary	456.40 FL	*- FL
17	2		*BOOTLID STOPPER	Not Necessary	49.60 FL	*- FL
18	1		*BOOTLID INSULATOR	Not Necessary	549.50 FL	*- FL
19	1		*BOOTLID LOCK	Damaged	339.80 FL	*339.80 FL
20	1		*BOOTLID CATCHER	Not Necessary	39.41 FL	*- FL
21	1		*BOOTLID WEATHERSTRIP	Cut	256.40 FL	*256.40 FL
22	1		*BOOTLID DETECTOR	Damaged	194.50 FL	*194.50 FL
23	1		*BOOTLID DETECTOR WIRE HARNESS	Not Necessary	469.60 FL	*- FL
24	1		*REAR END PANEL	Dented	651.70 FL	*651.70 FL
25	1		*REAR END PANEL TOP GARNISH	Deformed	296.20 FL	*296.20 FL
26	1		*REAR FLOOR PANEL TOP BOARD	Deformed	517.20 FL	*481.00 FL
27	1		*REAR FLOOR PANEL BOTTOM GARNISH	Not Necessary	496.80 FL	*- FL
28	1		*REAR FLOOR TOP SPONGE (CENTER)	Deformed	498.70 FL	*498.70 FL
29	1		*REAR NUMBER PLATE	Not Necessary	50.00 FS	*- FS
30	1		*SET REAR BUMPER CLIPS	Necessary	80.00 FS	*30.00 FS
31	1		*SET BOOTLID INSULATOR CLIP	Not Necessary	80.00 FS	*- FS
32	1		*SET TAILLAMP CLIPS	Not Necessary	30.00 FS	*- FS
33	1		*SET REAR FENDER COWLING CLIPS	Not Necessary	80.00 FS	*- FS
34	1		*SET REAR FENDER INNER TRIM CLIPS	Not Necessary	80.00 FS	*- FS
35	1		*BOOTLID SEALANT	Not Necessary	150.00 FS	*- FS
36	1		*SET BOOTLID INSULATOR CLIP	Not Necessary	80.00 FS	*- FS
37	1		*REAR END PANEL INSULATION SEAL	Necessary	80.00 FS	*60.00 FS
38	1		*SET REAR FLOOR PANEL BOTTOM GARNISH CLIP	Not Necessary	80.00 FS	*- FS

F=Franchise part. S=SpcNett. L=ListItemDisc.

Sub Total (\$\$)	14,258.01	5,657.10
- List Item Discount on L Items 25.00/25.00% (\$\$)	3,367.00	1,391.78
Total Parts (\$\$)	10,891.01	4,265.32

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
Labour Items				
1	PANEL BEATING REMOVAL AND REPLACING PARTS	New	1,600.00	800.00
2	TO SPRAY PAINT AFFECTED AREA	New	1,400.00	800.00
3	TUFF COAT	New	250.00	60.00
4	WIRING CHECK	New	180.00	30.00
5	REMOVE AND REFIX CUSHION SEAT /UPHOLSTRY AND ROOF LINING TO FACILITATE REPAIR	New	250.00	60.00
6	REMOVE AND REFIX REVERSE SENSOR AND DISTANCE SETTING	New	80.00	50.00
7	REMOVE AND REFIX REVERSE CAMERA AND DISTANCE SETTING	New	80.00	50.00
8	TRANSFER BOOTLID MECHANISM	New	80.00	60.00
9	CONDUCT WATER LEAKAGE TEST	New	80.00	0.00
10	TO CHECK DIAGNOSTICS OF VEHICLE MANAGEMENT /CONTROL UNITS ,RESET MEMORIES TO SPECIFICATION ETC	New	250.00	0.00
Gross Labour Cost (S\$)			4,250.00	1,910.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >