

LKK Auto Consultants Pte Ltd (Co.Reg.No:199607198R)

51 Ubi Ave 1 #01-25, Paya Ubi Industrial Park

Singapore 408933

Tel: 6256-3561 Fax: 6844-8805 Email: sur@lkkauto.com; assignments@lkkauto.com; cs-a@lkkauto.com; admin-a@lkkauto.com

VEHICLE DAMAGE INSPECTION REPORT

AIG Asia Pacific Insurance Pte. Ltd.
AIG Building, 78 Shenton Way, #09-16
Singapore 079120

Our File No: CC3/AIG22012012/AVCM4**Date:** 03/04/2023**REFERENCE**

Insured/Claimant:	KWOK TIAN CHEE	Policy No:	1800088216-03
Date of Loss:	23/11/2022	Nature of Claim:	OD
		Claim No:	3477053525SG

DESCRIPTION & IDENTIFICATION OF VEHICLE

Reg No:	SJJ3920D		
Make & Model:	AUDI A3, 999cc SEDAN TFSI S TRONIC (LED) (A)	Engine No:	CHZ466306
Reg. Date:	26/07/2018 (Man. Year: 2018)	Chassis No:	WAUZZZ8V9J1069554
Colour:	Red	Odometer:	55945 km
Engine Capacity:	999 cc		
Market Value/New Car Price:	S\$94,000.00		
Sum Insured (S\$):	Market Value/New Car Price		

CONDITION OF VEHICLE AT THE TIME OF SURVEY

General Condition:	Steering (Serviceable):	Yes	Footbrake (Serviceable):	Yes
Handbrake (Serviceable):	Yes	Engine Modification:	No	Pre-accident Condition:

CONDITION OF TYRES

Front Tyre Size:	205/55 R16	Rear Tyre Size:	205/55 R16
Front Left Side:	Pirelli 6 mm	Rear Left Side:	Pirelli 6 mm
Front Right Side:	Pirelli 6 mm	Rear Right Side:	Pirelli 6 mm

The above values represent the remaining tyre treads depth

COST OF CLAIMS	Repairer's	Adjuster's	Difference	Diff %
Parts	13,133.00	3,860.88	9,272.12	70.60
Miscellaneous Items	0.00	0.00	0.00	
Labour	5,282.00	2,572.00	2,710.00	51.31
Paintwork Labour	0.00	0.00	0.00	
Towing	0.00	0.00	0.00	
Calculated Gross Total (S\$)	18,415.00	6,432.88	11,982.12	65.07
- Excess (S\$)	500.00	500.00	0.00	0.00
(S\$)	17,915.00	5,932.88	11,982.12	66.88
+ GST 8.00/8.00% (S\$)	1,433.20	474.63	958.57	66.88
Nett Amount (S\$)	19,348.20	6,407.51	12,940.69	66.88

INSPECTION

Date of Assignment:	01/12/2022		
Date Inspected:	30/11/2022	Inspected At:	Premium Automobiles Pte Ltd (UBI) 55 Ubi Road 1 Singapore 408699
Estimated Period of Repair:	5.0 days		

Adjuster: ADRIAN LING**Manager:** VERON CHEN

NOTE: This report represents our findings at the time and place of inspection stated herein. Such inspection has been carried out to the best of our knowledge and ability but any other liability under any other circumstances is hereby expressly excluded.

REPAIR DETAILS

Recommended Parts

No.	Qty	Part No.	Particulars	Condition	Repairer's	Amount
1	1		*FRONT BUMPER	Deformed	2,432.00 FS	*1,945.60 FS
2	1		*FRONT BUMPER GUIDE SECTION - LH	Not Necessary	43.00 FS	*- FS
3	1		*FRONT BUMPER CLOSING ELEMENT - LOWER CENTRE	Not Necessary	571.00 FS	*- FS
4	1		*FRONT BUMPER CLOSING ELEMENT - LH	Not Necessary	318.00 FS	*- FS
5	1		*FRONT BUMPER TRIM COVER - LH	Not Necessary	182.00 FS	*- FS
6	1		*FRONT WHEEL HOUSING LINER ADAPTER - LH	Not Necessary	42.00 FS	*- FS
7	1		*FRONT BUMPER AIR GUIDE GRILLE - LH	Not Necessary	210.00 FS	*- FS
8	1		*FRONT FENDER - LH	Dented	954.00 FS	*763.20 FS
9	5		*FRONT FENDER RIVET	Necessary	19.00 FS	*15.20 FS
10	1		*FRONT FENDER ATTACHMENT PARTS	Not Necessary	75.00 FS	*- FS
11	1		*FRONT FENDER BRACKET - LH CENTER	Not Necessary	46.00 FS	*- FS
12	1		*FRONT FENDER BRACE	Bent	107.00 FS	*85.60 FS
13	1		*FRONT FENDER BRACKET - LH	Not Necessary	31.00 FS	*- FS
14	1		*FRONT WHEEL HOUSING LINER - LH	Not Necessary	183.00 FS	*- FS
15	1		*FRONT ALUMINIUM RIM	Cut	1,303.00 FS	*1,042.40 FS
16	1		*FRONT ALUMINIUM RIM RUBBER VALVE	Necessary	4.00 FS	*2.96 FS
17	1		*HEADLIGHT - LH	Not Necessary	5,879.00 FS	*- FS
18	1		*LIFT CYLINDER - LH	Not Necessary	156.00 FS	*- FS
19	1		*LIFT CYLINDER HOSE	Not Necessary	78.00 FS	*- FS
20	1		*SUNDRIES	Necessary	500.00 FS	*5.92 FS

F=Franchise part. S=SpcNett.

Total Parts (S\$) 13,133.00 3,860.88

Report was unsubmitted during this print-out.

Recommended Miscellaneous Items

There are no new miscellaneous items selected.

Recommended Labour

No	Particulars	Lab.Type	Repairer's	Amount
Labour Items				
1	TO REMOVE, CHECK AND REINSTALL FRONT WIRE HARNESS FOR HEADLIGHTS, HORNS, OUTSIDE TEMPERATURE SENSOR AND HEADLIGHT WASHER ASSY	New	360.00	0.00
2	TO REMOVE AND TRANSFER LHS HEADLIGHTS CONTROL UNIT AND POWER MODULE	New	350.00	0.00
3	TO DISMANTLE AND RENEW FRONT BUMPER, LHS FRONT FENDER AND LHS HEADLIGHT. RE-ORGANIZE CRASH MANAGEMENT COMPONENTS. REINSTALL ALL PARTS REMOVED	New	2,100.00	1,000.00
4	TO RESPRAY FRONT BUMPER AND LHS FRONT FENDER	New	2,000.00	1,100.00
5	TO RENEW LHS FRONT RIM AND CARRY OUT WHEEL ALIGNMENT	New	280.00	280.00
6	TO CARRY OUT DIAGNOSTIC CHECK	New	192.00	192.00
Gross Labour Cost (S\$)			5,282.00	2,572.00

Report was unsubmitted during this print-out.

< END OF ESTIMATES >