



LKK Auto Consultants Pte Ltd

51 Ubi Ave 1 #01-25 Paya Ubi Industrial Park, Singapore 408933

TEL: 6256 3561 FAX: 6256 4315

Reg. No: 199607198R GST Reg. No. 19-9607198-R

Affiliated to Federation Internationale Des Experts En Automobile			
ALLIED WORLD ASSURANCE COMPANY LTD (SINGAPORE BRANCH) 60 ANSON ROAD #08-01 (8th FLOOR) MAPLETREE ANSON SINGAPORE 079914		Ref: CS/AWA22008778/Ecy3e2-1 Date: 24/03/2023 Code: AWA	
1. Policy Particulars :- OWN DAMAGE			
Insured Veh.	XE 6903U	Veh. Inspected	RIGID TANKER
Policy No.	BVFCB0007172215	Coverage (\$)	70,000.00
Claim No.	NSV2200131/PC	Excess (\$)	0.00
Assign From	GOH STELLA	Assign Date	06/09/2022
2. Vehicle Particulars & Condition			
Make & Model	c.c 0		
Engine No.	Year of Reg.		
Chassis No.	Colour		
Odometer	Steering		
Brakes	Modification		
General			
3. Conditions of Tyres			
	Size	Make	Balance
R/H Front Tyre			mm
L/H Front Tyre			mm
R/H Rear Tyre			mm
L/H Rear Tyre			mm
4. Description of Damages			
THE RIGID TANKER SUSTAINED DAMAGES AT THE REAR PORTION. DAMAGES SEE DETAILS.			
5. General Information			
Accident Date	22/08/2022	Inspection Date	13/09/2022
Survey held at	24 JALAN BUROH SINGAPORE 619480		
Repairer	SSB CRYIGENIC EQUIPMENT PTE LTD		
5a. Remarks			
A)THE MARKET VALUE IS S\$145,000.00(EST. AVERAGE) B)IN ACCORDANCE TO YOUR INSTRUCTIONS, WE HAVE AUTHORISED REPAIRS.			
5b. Estimate Days of Repair			
ESTIMATED NORMAL PERIOD FOR REPAIR:		25 Working Days	

SSB CRYOGENIC EQUIPMENT PTE LTD

<u>Qty</u>	<u>Description</u>	<u>Condition</u>	<u>Estimate</u>	<u>Recommendation</u>
1	Lot Tank survey	Necessary	\$ 300.00	\$ 300.00
1	Lot Break vacuum for welding works	Necessary	\$ 300.00	\$ 300.00
1	Pcs Replacement of diversion valve	Necessary	\$ 2,000.00	\$ 2,000.00
2	Pcs Replacement of flexible hose	Bent	\$ 600.00	\$ 600.00
1	Lot Manpower charges for Replacement of pump (AL supply)	Necessary	\$ 500.00	\$ 500.00
1	Pcs Replacement of vacuum probe (Hasting) (DV-6R)	Necessary	\$ 250.00	\$ 250.00
1	Lot Installation of piping support with welding works	Necessary	\$ 600.00	\$ 600.00
4	Pcs Replacement of Herose SRV (3 bar)	Necessary	\$ 3,600.00	\$ 3,600.00
1	Lot Refurbish of pipeline for ISO Tank	Necessary	\$ 3,000.00	\$ 3,000.00
1	Lot Refrabrication of ventline	Necessary	\$ 2,000.00	\$ 2,000.00
1	Lot Purging of ISO tank (LIN) & pressure test	Necessary	\$ 1,000.00	\$ 1,000.00
1	Lot Vacuum pulling	Necessary	\$ 2,000.00	\$ 2,000.00
4	Pcs SRV pop testing with in-house Certificate	Necessary	\$ 150.00	\$ 150.00
1	Lot Canopy repairs	Dented	\$34,000.00	\$34,000.00
1	Lot Sandblasting and painting of ISO tank	Necessary	\$ 2,500.00	\$ 2,500.00
1	Lot Testing and commission of road tanker	Necessary	\$ 1,000.00	\$ 1,000.00
1	Lot BV recertification	Necessary	\$ 1,500.00	\$ 1,500.00
			Total (A) :	\$55,750.00 =====

RPM ELECTRICAL ENGINEERING PTE LTD

<u>Labour Charges</u>	<u>Estimate</u>	<u>Recommendation</u>
1) Supply skilled labour and necessary instruments to disconnect power and control cable, dismantle out for repair c/w rewiring after completion	\$5,580.00	\$5,580.00
Job include material supplied as follows:-		
a) Emergency Push Button, CSE121209P/WPBERR0 – 1pc		
b) S/S enclosure 700 x 500 x 250mm – 1pc		
c) Neoprene cable 4C x 16mm ² - 17meters		
d) 4-Pin 63Amp plug – 1pc		
e) Change over switch 63A/4pole (A619) – 1pc		
f) Metal angle bar/flat bar (bracket for cable storage enclosure)		
	Total (B) :	\$5,580.00



AIR LIQUID SINGAPORE PTE LTD

<u>Qty</u>	<u>Description of Parts</u>		<u>Estimate</u>	<u>Recommendation</u>
1	Overfilling Trailer Protection	USD	\$1,400.00	\$1,400.00
1	DAP Singapore	USD	\$ 170.00	\$ 170.00
			USD	<u>\$1,570.00</u> =====

USD convert to SGD at 1.42 as at 14/10/2022 of invoice

\$2,229.40
=====

Note: The repair done by RPM Electrical Engineering Pte Ltd

<u>Qty</u>	<u>Description of Parts</u>	<u>Condition</u>		<u>Estimate</u>	<u>Recommendation</u>
1	GBS 155/4,5 Part No: CEP02GEN	Broken	EUR	\$11,501.00	\$11,501.00
				EUR	<u>\$11,501.00</u> =====

EUR convert to SGD at 1.39 as at 29/08/2022 of invoice

\$15,986.39
=====

Note: The repair done by SSB Cryogenic Equipment Pte Ltd


Total (C) : **\$18,215.79**
=====

Recommended Cost of Repair (Rigid Tanker) (A + B + C)	\$79,545.79
Less Owner's Contribution	- \$ 9,545.79
Nett Liability	\$70,000.00 =====

(SIN DOLLARS: Seventy Thousand Only)

We recommend that the repairs of the entire damage require about 25 (Twenty-Five) working days to complete.

Vehicle Inspected By:



CHEN TSUE YEE
Automotive Assessor

DISCLAIMER OF LIABILITY TO THIRD PARTIES:- This Report is made solely for the use and benefit of the Client named on the front page of this Report. No liability or responsibility whatsoever, in contract or tort, is accepted to any third party who may rely on the Report wholly or in part. Any third party acting or relying on this Report, in whole or in part, does so at his or her own risk.